

FINNING (UK) LTD,
688-689 Stirling Road
Slough
Berkshire
SL1 4ST
Telephone: 01753 497300
Fax: 01753 497398

Termination Points, Assumptions & Exclusions

Gas Supply	Gas train supplied for unit only, connection to site gas supply by others.
HV Termination	No HV included
LV Termination	Main Power will be terminated at the LIMA control panels.
Exhaust	Outlet of exhaust silencer until site stack requirements have been agreed.
Cooling Systems	Closed loop heat rejection system with floor or roof mounted radiators.
For CHP Option	Inlet/Outlet connections on container for connection to site by others.
Ventilation	Inlet/outlet attenuators on the acoustic container.
Noise Levels	The system has been designed to achieve a noise break out level of 75 dB(A) + 2dB(A) tolerance based on 6 measurement points around the container at 1.5M measurement height based on DIN 45635.
Oil Supply	Bulk oil supply tanks with retractable hoses within 10 meters of the container. Offered as optional extra
Top up Water	Supplied by others to be piped to the CHP.
Telephone Connections	Supplied by others to the control panels.
Access	We have assumed that clear access to site is available within normal working hours. Offloading and positioning is offered as an optional extra and assumes Lorries and cranes can be located next to the unit locations.
Gas Quality	We have assumed the gas will meet the CATERPILLAR schedule for fuel gases.
Site Civils & Earthing	All by others, engine plinths to be to Finning specifications.